

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
LEAKE COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Leake County, Mississippi at the Leake County Chamber of Commerce, 103 N. Pearl St. Carthage, MS Mississippi, until 9:00 am on the 3rd day of June, 2019 and shortly thereafter publicly opened for the construction of 0.121 miles of REPLACE BRIDGE AND APPROACHES on the JACK BOOT ROAD being known as Project No. LSBP-40(17) in Leake County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE @ STA. 61+16	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	816.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	1,845.000	CY
GRANULAR MATERIAL, (CLASS 3, GROUP "B")	674.000	TON
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	0.840	CY
18" REINFORCED CONCRETE PIPE, CLASS III	80.000	LF
18" REINFORCED CONCRETE PIPE, END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	5.260	TON
COMMERCIAL FERTILIZER (13:13:13)	0.790	TON
AMMONIUM NITRATE	0.180	TON
SEEDING	2.630	AC
VEGETATIVE MATERIALS FOR MULCH	7.890	TON
EXCELSIOR BLANKET	300.000	SY
PORTLAND CEMENT CONCRETE	7.558	CY
PAVED DITCH		
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	1,200.000	LF

SECTION 900
 PROJECT NO. LSBP-40(17)
 LEAKE COUNTY

WATTLES, 20"	300.000	LF
LOOSE RIPRAP, 200 LB.	965.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21 - 0.43	2,030.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	990.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
14" PRESTRESSED CONCRETE PILING CUT OFF	0.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	24.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' CURB	8.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' CURB	2.000	EA
BEAM TYPE RAILING WITH CONCRETE POSTS	214.000	LF
29.00' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	4.000	EA
29.00' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
7.50' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	80.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21 - 0.43	168.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Leake County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from J. Christian Gardner, LSBP Engineer for Leake County, Mississippi, P. O. Drawer A, Indianola. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Leake County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Tony Smith, President
Leake County Board of Supervisors